



PROJECT NAME	Warehouse 60m × 80m	PROJECT TYPE	Industrial Warehouse / Factory
CLIENT NAME	[Client Name]	LOCATION	Cambodia
CONTRACT PACKAGE	Structural & Civil Works	BUILDING AREA	4,800 m²
PREPARED BY	QS Department	CURRENCY	USD (1 USD = 4,100 KHR)
STATUS	Preliminary for Client Review	EAVE HEIGHT / ROOF	9.0m / Lock-Seam 0.5mm, i=15%

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (USD)	AMOUNT (USD)
1 — SITE PREPARATION					
1.1	Set-out and surveying (lump sum)	LS	1.00	1,500.00	1,500.00
2 — PILING WORKS					
2.1	Precast RC Pile 300×300mm, L=6.0m — Supply	m	648.00	16.00	10,368.00
2.2	Precast RC Pile 300×300mm, L=6.0m — Drive/Install	m	648.00	10.50	6,804.00
2.3	Pile head cut and preparation (108 nos)	nos	108.00	25.00	2,700.00
2.4	Pile load test (allow 2 nos dynamic test)	nos	2.00	800.00	1,600.00
3 — EXCAVATION & EARTHWORKS					
3.1	Machine excavation — pile caps and tie beams	m³	284.65	8.50	2,419.54
3.2	Disposal of surplus spoil (off-site trucking)	m³	150.00	6.00	900.00
3.3	Backfill and compact with approved material	m³	151.79	9.00	1,366.15
3.4	Laterite sub-base fill 300mm (for ground slab)	m³	1,440.00	Owner	0.00
3.5	Sand bedding 100mm under slab	m³	480.00	7.50	3,600.00
4 — LEAN CONCRETE (C10, 50MM BLINDING)					
4.1	Lean concrete C10 — under pile caps and tie beams	m³	25.15	90.00	2,263.14
4.2	Lean concrete C10 — under sidewalk (280 m² × 50mm)	m³	14.00	90.00	1,260.00
5 — REINFORCED CONCRETE — PILES					
5.1	Precast pile concrete already in pile rate (see item 2)	LS	1.00	0.00	0.00
6 — REINFORCED CONCRETE — PILE CAPS (C30)					
6.1	RC C30 — EC Pile Caps (18 nos, 12.96 m³)	m³	12.96	165.00	2,138.40
6.2	RC C30 — C1 Pile Caps (18 nos, 15.55 m³)	m³	15.55	165.00	2,566.08
6.3	RC C30 — C2 Pile Caps (9 nos, 25.20 m³)	m³	25.20	165.00	4,158.00
7 — REINFORCED CONCRETE — TIE BEAMS (C25)					
7.1	RC C25 — Perimeter Tie Beams (42.0 m³)	m³	42.00	155.00	6,510.00
7.2	RC C25 — Interior Tie Beams Row E (12.0 m³)	m³	12.00	155.00	1,860.00
8 — REINFORCED CONCRETE — PEDESTALS (C25)					

ITEM NO.	DESCRIPTION	UNIT	QTY	RATE (USD)	AMOUNT (USD)
8.1	RC C25 — Pedestals 400×400×500mm (45 nos, 3.60 m³)	m³	3.60	155.00	558.00
9 — GROUND FLOOR SLAB (C25, 150MM)					
9.1	RC C25 ground slab 150mm — concrete only (720 m³)	m³	720.00	150.00	108,000.00
9.2	BRC Mesh A10 @ 200×200 — slab (17,040 kg)	ton	17.04	1,200.00	20,448.00
9.3	PE membrane 0.2mm polyethylene (5,040 m²)	m²	5,040.00	0.80	4,032.00
9.4	Saw-cut joints @ 6m×6m grid (2,080 lm)	m	2,080.00	0.80	1,664.00
9.5	Surface hardener / power float finish	m²	4,800.00	2.50	12,000.00
10 — REINFORCEMENT STEEL — FOUNDATION (SD40)					
10.1	Rebar SD390 — Pile rebar (5,886 kg)	ton	5.89	950.00	5,591.70
10.2	Rebar SD390 — Pile cap rebar (6,445 kg)	ton	6.45	950.00	6,123.17
10.3	Rebar SD390 — Tie beam rebar (7,560 kg)	ton	7.56	950.00	7,182.00
10.4	Rebar SD390 — Pedestal rebar (468 kg)	ton	0.47	950.00	444.60
10.5	Binding wire allowance (@ 1.5% of rebar wt)	kg	305.00	1.50	457.50
11 — FORMWORK					
11.1	Formwork — Pile caps EC & C1 (103.68 m²)	m²	103.68	17.00	1,762.56
11.2	Formwork — Pile caps C2 (50.40 m²)	m²	50.40	17.00	856.80
11.3	Formwork — Tie beams sides (360.0 m²)	m²	360.00	17.00	6,120.00
11.4	Formwork — Pedestals (36.0 m²)	m²	36.00	17.00	612.00
12 — PERIMETER SIDEWALK (RC C25, 120MM)					
12.1	RC C25 sidewalk concrete 100mm	m³	33.60	120.00	4,032.00
12.2	BRC Mesh A7 sidewalk (624 kg)	ton	0.62	1,200.00	749.28
12.3	Sidewalk formwork and edge trim (280 lm)	m	280.00	6.00	1,680.00
12.4	Surface finish — broomed texture	m²	280.00	2.00	560.00
13 — MASONRY WORKS					
13.1	200mm concrete block wall (943 m²)	m²	943.00	27.00	25,461.00
13.2	Mortar mix and accessories	LS	1.00	800.00	800.00
14 — PLASTERING & FINISHES					
14.1	Internal plaster 20mm	m²	943.00	7.00	6,601.00
14.2	External plaster 20mm	m²	943.00	8.50	8,015.50
14.3	Internal paint — 2 coats emulsion + primer	m²	943.00	4.50	4,243.50
14.4	External paint — 2 coats masonry paint + primer	m²	943.00	5.50	5,186.50
15 — OPENINGS — DOORS, SHUTTERS, WINDOWS					
15.1	Roller shutters motor-operated 4.0×4.5m (8 nos)	nos	8.00	2,100.00	16,800.00
15.2	Steel personnel door 1.0×2.1m, painted (4 nos)	nos	4.00	40.00	160.00
15.3	Aluminium Glass Window 1.2×3m (36 nos, 129.6 m²)	m²	129.60	80.00	10,368.00
Total Direct Construction Cost				312,522.00 USD	

SCOPE INCLUDED

- Pile Foundation (Precast RC 300×300, L=6m)
- Pile Caps (EC-2pile, C1-2pile, C2-4pile)
- Ground Beams / Tie Beams
- Pedestals
- Ground Floor Slab (150mm RC C25)
- Sidewalk (1.0m wide × 120mm RC)
- Excavation & Backfill
- Lean Concrete (50mm C10)
- Reinforcement Steel (SD40)
- Formwork
- Masonry Walls (200mm block base)
- Plastering & Paint
- Roller Shutters, Steel Doors, Louvers
- Gutter, Downpipe, Ridge Cap, Flashing

SCOPE EXCLUDED

- All Steel Structure: Columns, Rafters, Trusses, Purlins, Bracing
- Roof Sheets & Metal Cladding (supplied under steel contract)
- Mechanical, Electrical & Plumbing (MEP)
- Site clearance, boundary wall, external roads
- Soil investigation (assumed)

NOTES & ASSUMPTIONS

1. All rates are in USD. Exchange rate: 1 USD = 4,100 KHR (June 2026).
2. Laterite sub-base fill (Item 3.4) is by Owner — excluded from contractor cost.
3. Steel structure and roofing are under a separate contract package.
4. Quantities are preliminary and subject to final design confirmation.
5. This BOQ is for tender/estimation purposes — preliminary for client review.

Prepared By
Quantity Surveyor

Checked By
Senior QS / Project Manager

Approved By
Director